



Addendum No. 1

RFP 21-06 Yuba College, Sutter Campus, LED Monument Signs

Date: 01/13/2022

Clarifications:

1. **Yuba College West Parking Lot Sign:** Provide the same size and look as the new sign at Woodland Community College. Build-up the subgrade and compact it. Use 12” layers of road base or other material that can be compacted and provide a long-term solution. Compact it to 95%. Move the four large boulders to protect the sign from vehicle damage. Level the ground in front of and on the sides of the monument sign and install (very securely) green artificial turf.
2. **Yuba College North Beale Roadway Sign:** Provide the same size and look as the new sign at Woodland Community College. Build up the sign subgrade and compact it to create a better visual affect. Locate the sign as close as is reasonable to North Beale Road without encroaching into the easements. Run the new underground electrical service from the panel at building 200 up through the building down and underground at the exterior water drain and directionally bored under the roadway, then trenched to the new sign. Locate all utilities using a third party locating firm and with close coordination with Bryan Epp.
3. **Include electrical power conditioning features in the new signs.** The power tends to be very poor quality at times and can damage sensitive equipment.
4. **Include three sets of 3/8” thick LEXAN protective panels rated for UV to not yellow and as spares to the existing panels to be attached to the new signs.** This feature is to protect the signs from vandalism and damage from rocks.
5. **Secure the signs so that they cannot be removed from the campus.** Ensure that the signs are well attached to the concrete base. If possible, add a feature that notifies the College if the signs are no longer working.
6. **Provide the standard spare parts packages for each sign.**

The End.